

PLANT MATERIAL SCHEDULE

TOTAL TREE

COUNT

TREES						
TYPE	QTY	COMMON NAME	BOTANICAL NAME	SIZE	REMARKS	
CE	9	Cedar Elm	Ulmus crassifolia	3" cal.	B&B, 13' ht., 5' spread min., 5' clear trunk	
LO	21	Live Oak	Quercus virginiana	3" cal. 3" cal.	container, 14' ht., 6' spread, 5' clear straight tru container, 14' ht., 6' spread, 5' clear straight tru	
RO	2	Red Oak	Quercus shumardii			
CM 11 Crape Myrtle		Lagerstroemia indica 6'-8' ht.		container, 3 or 5 trunks, tree form		
SHRUBS						
TYPE	QTY.	COMMON NAME	BOTANICAL NAME	SIZE	REMARKS	
DYH IH NPH NRS	110 36 315 16	Dwarf Yaupon Holly Indian Hawthorn 'Clara' Needlepoint Holly Nellie R. Stevens Holly	Ilex vonitoria 'nana' Rhaphiolepis indica 'Clara' Ilex comuta 'Needlepoint' Ilex x 'Nellie R. Stevens'	3 gal. 3 gal. 5 gal. 4' ht.	container, 18" ht., 18" spread container, 18" ht., 18" spread container, 24" ht., 20" spread container, 36" spread, full to base	
GROUNE	COVERS					
TYPE	QTY	COMMON NAME	BOTANICAL NAME	SIZE	REMARKS	
SC	160	Seasonal Color '419' Bermudagrass	Cynodon dactylon '419'	4" pots	selection by owner, 10" o.c. Solid Sod refer to notes	

NOTE: Plant list is an aid to bidders only. Contractor shall verify all quantities on plan. All heights and spreads are minimums. All plant material shall meet or exceed remarks as indicated. All trees to have straight trunks and be matching within varieties.

THERE ARE NO EXISTING TREES ON SITE

GENERAL LAWN NOTES

- 1. FINE GRADE AREAS TO ACHIEVE FINAL CONTOURS INDICATED ON CIVIL
- 2. ADJUST CONTOURS TO ACHIEVE POSITIVE DRAINAGE AWAY FROM BUILDINGS. PROVIDE UNIFORM ROUNDING AT TOP AND BOTTOM OF SLOPES AND OTHER BREAKS IN GRADE. CORRECT IRREGULARITIES AND AREAS WHERE WATER MAY STAND.
- 3. ALL LAWN AREAS TO RECEIVE SOLID SOD SHALL BE LEFT IN A MAXIMUM OF 1" BELOW FINAL FINISH GRADE. CONTRACTOR TO COORDINATE OPERATIONS WITH ON-SITE CONSTRUCTION MANAGER.
- 4. IMPORTED TOPSOIL SHALL BE NATURAL, FRIABLE SOIL FROM THE REGION, KNOWN AS BOTTOM AND SOIL, FREE FROM LUMPS, CLAY, TOXIC SUBSTANCES, ROOTS, DEBRIS, VEGETATION, STONES, CONTAINING NO SALT AND BLACK TO BROWN IN COLOR.
- 5. ALL LAWN AREAS TO BE FINE GRADED, IRRIGATION TRENCHES
 COMPLETELY SETTLED, AND FINISH GRADE APPROVED BY THE OWNER'S
 CONSTRUCTION MANAGER OR ARCHITECT PRIOR TO INSTALLATION.
- 6. ALL ROCKS 3/4" DIAMETER AND LARGER, DIRT CLODS, STICKS, CONCRETE SPOILS, ETC. SHALL BE REMOVED PRIOR TO PLACING TOPSOIL AND ANY LAWN INSTALLATION
- CONTRACTOR SHALL PROVIDE (1") ONE INCH OF IMPORTED TOPSOIL ON ALL AREAS TO RECEIVE LAWN.

SOLID SOD NOTES

- 1 FINE GRADE AREAS TO ACHIEVE FINAL CONTOURS INDICATED.
 LEAVE AREAS TO RECEIVE TOPSOIL 3" BELOW FINAL DESIRED
 GRADE IN PLANTING AREAS AND 1" BELOW FINAL GRADE IN TURF
 AREAS
- 2. ADJUST CONTOURS TO ACHIEVE POSITIVE DRAINAGE AWAY FROM BUILDINGS. PROVIDE UNIFORM ROUNDING AT TOP AND BOTTOM OF SLOPES AND OTHER BREAKS IN GRADE. CORRECT IRREGULARITIES AND AREAS WHERE WATER MAY STAND.
- 3. ALL LAWN AREAS TO RECEIVE SOLID SOD SHALL BE LEFT IN A MAXIMUM OF 1" BELOW FINAL FINISH GRADE. CONTRACTOR TO COORDINATE OPERATIONS WITH ON-SITE CONSTRUCTION MANAGER.
- 4. CONTRACTOR TO COORDINATE WITH ON-SITE CONSTRUCTION MANAGER FOR AVAILABILITY OF EXISTING TOPSOIL.
- 5. PLANT SOD BY HAND TO COVER INDICATED AREA COMPLETELY. INSURE EDGES OF SOD ARE TOUCHING. TOP DRESS JOINTS BY HAND WITH TOPSOIL TO FILL VOIDS.
- 6. ROLL GRASS AREAS TO ACHIEVE A SMOOTH, EVEN SURFACE, FREE FROM UNNATURAL UNDULATIONS.
- 7. WATER SOD THOROUGHLY AS SOD OPERATION PROGRESSES.
- 8. CONTRACTOR SHALL MAINTAIN ALL LAWN AREAS UNTIL FINAL ACCEPTANCE. THIS SHALL INCLUDE, BUT NOT LIMITED TO: MOWING, WATERING, WEEDING, CULTIVATING, CLEANING AND REPLACING DEAD OR BARE AREAS TO KEEP PLANTS IN A VIGOROUS, HEALTHY CONDITION.
- 9. CONTRACTOR SHALL GUARANTEE ESTABLISHMENT OF AN ACCEPTABLE TURF AREA AND SHALL PROVIDE REPLACEMENT FROM LOCAL SUPPLY IF NECESSARY.
- 10. IF INSTALLATION OCCURS BETWEEN SEPTEMBER 1 AND MARCH 1, ALL SOD AREAS TO BE OVER-SEEDED WITH WINTER RYEGRASS, AT A RATE OF (4) POUNDS PER ONE THOUSAND (1000) SQUARE FEET.

TEL:817-538-9258

LANDSCAPE TABULATIONS: AVID HOTEL

LANDSCAPE AREA STANDARDS

Requirements: 5% of site area to be landscape.

Lot area: 79,183 s.f.

Required Provided 3,395 s.f. 13,673 s.f.

Requirement: 1 Tree every 30 LF of street frontage 592 l.f. of street frontage

(20) trees (20) 3" cal. trees

PARKING LOT SCREENING PROVIDED

LANDSCAPE NOTES


- CONTRACTOR SHALL VERIFY ALL EXISTING AND PROPOSED SITE ELEMENTS AND NOTIFY ARCHITECT OF ANY DISCREPANCIES. SURVEY DATA OF EXISTING CONDITIONS WAS SUPPLIED BY OTHERS.
- 2. CONTRACTOR SHALL LOCATE ALL EXISTING UNDERGROUND UTILITIES AND NOTIFY ARCHITECT OF ANY CONFLICTS. CONTRACTOR SHALL EXERCISE CAUTION WHEN WORKING IN THE VICINITY OF UNDERGROUND UTILITIES.
- 3. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL REQUIRED LANDSCAPE AND IRRIGATION PERMITS.
- 4. CONTRACTOR TO PROVIDE A MINIMUM 2% SLOPE AWAY FROM ALL
- 5. ALL PLANTING BEDS AND LAWN AREAS TO BE SEPARATED BY STEEL EDGING. NO STEEL TO BE INSTALLED ADJACENT TO SIDEWALKS OR
- 6. ALL LANDSCAPE AREAS TO BE 100% IRRIGATED WITH AN UNDERGROUND AUTOMATIC IRRIGATION SYSTEM AND SHALL INCLUDE RAIN AND FREEZE SENSORS.
- 7. ALL LAWN AREAS TO BE SOLID SOD BERMUDAGRASS, UNLESS OTHERWISE NOTED ON THE DRAWINGS.

BOU	BOUNDARY LINE DATA					
LINE NO.	BEARING	DISTANCE				
L1	N 89°13'15" E	91.96'				
L2	S 00°26'27" E	586.16'				
L3	S 89°01'02" W	9.55'				
L4	S 89°01'02" W	190.69'				
L5	S 00°58'58" E	40.00'				
L6	N 00°58'58" W	28.24'				

OWNER DIPLOMAT GROUP LLC 3512 SAN LUCAS LANE DENTON, TX 76208 CONTACT: KAMLESH PATEL TEL: 214-335-7117	SURVEYOR A & W SURVEYORS, INC P.O.BOX 870029 MESQUITE, TEXAS 75187 CONTACT: JOHN TURNER, R.P.L.S. TEL: 972-681-4975
ENGINEER TRIANGLE ENGINEERING LLC 1503 ASTORIA DRIVE ALLEN, TEXAS 75013 CONTACT:KARTAVYA PATEL	ARCHITECT RSS ARCHITECTS, LLC 103 S.MESQUITE STREET,SUITE B ARLINGTON,TX 76010 CONTACT: SHANE SIGRIST

TEL: 214-609-9271

		CURVE DATA TABLE					
ı		NO.	LENGTH	RADIUS	DELTA	CH BEARING	CH LENGTH
		C1	38.41'	868.71'	2°31'59"	S 89°30'54" E	38.40'
		C2	109.15'	60.00'	104°13'37"	N 85°19'38" W	94.71'
		С3	24.33'	30.00'	46°27'28"	S 65°47'18" W	23.66'
		C4	47.12'	30.00'	90°00'00"	N 45°58'58" W	42.43'
		C5	229.88'	293.00'	44°57'09"	N 21°29'36" E	224.03'
		C6	280.00'	357.00'	44°57'09"	N 21°29'36" E	272.96'
		C7	48.55'	30.00'	92°43'40"	N 45°22'52" E	43.42'
	L					-	



LANDSCAPE ARCHITECT STUDIO GREEN SPOT, INC. 1333 W. McDERMOTT DR. ALLEN, TEXAS 75013 (469) 369-4448

(469) 369-4448
CHRIS@STUDIOGREENSPOT.COM



CITY OF FARMERS BRANCH, TEXAS

DALLAS COUNTY, TEXAS

...

AVID

FOR APPROVAL 02.27.2018
CITY COMMENTS 03.27.2018
CITY COMMENTS 04.14.2018

CITY COMMENTS 04.14.2018
CITY COMMENTS 08.23.2018

DATE: 08.23.2018

SHEET NAME: LANDSCAPE PLAN

SHEET NUMBER:

L.